

RESOLUTION NO 20-03 OF THE
BOARD OF DIRECTORS OF THE INTERIM BORREGO SPRINGS WATERMASTER Establishing Criteria for
Verification of Meter Calibration, Installation, and Accuracy

WHEREAS, the Settlement Agreement, Stipulated Judgment and Rules & Regulations of the Interim Borrego Springs Watermaster (“Watermaster”) require pumpers with Baseline Pumping Allocations to install Watermaster approved meters.

WHEREAS, the Watermaster adopted Resolution No. 20-02 establishing a list of approved meters on March 30, 2020.

WHEREAS, the Stipulated Judgment and Rules & Regulations require that upon installation, and annually thereafter, each pumper shall arrange for the manufacturer or qualified installer of such approved meters to provide written verification to the Watermaster of the ongoing accuracy of the meter readings and meter calibration.

WHEREAS, per section 5.1 of the Watermaster Rules & Regulations, the Watermaster or its designee shall provide forms to submit proof of meter installations.

WHEREAS, the first meter reading will be collected by October 1, 2020 and written verification of meter accuracy for existing and new wells must be submitted to Watermaster prior to the first meter read .

NOW, THEREFORE, be it resolved by the Board of Directors of the Interim Borrego Springs Watermaster, as follows:

1. The Board of Directors hereby approves the attached Exhibit 1 as the list of information that must be submitted to the Watermaster as qualifying proof of meter calibration and installation.
2. The Board of Directors hereby approves the attached Exhibit 2 as the list of information that must be submitted to the Watermaster to verify the accuracy of meter readings.
3. The Board of Directors hereby directs the Technical Consultant to maintain and publish to the Watermaster website a list of approved third-party vendors that can provide verification of meter installation and accuracy when these services are not performed by the manufacturers of the approved meter types.

PASSED AND ADOPTED at a regular meeting of the Board of Directors of the Interim Borrego Springs Watermaster held on the 27th day of August 2020, by the following vote:

AYES: Duncan, Seley, Bennett, Smith, Deichler

NOES:

ABSENT:

President
Board of Directors

Secretary
ATTEST

Exhibit 1
Requisite Information to Demonstrate Proof of Meter Calibration and Installation to the Borrego Springs Watermaster

For all new meter installations, the following information must be submitted to the Watermaster as proof of meter calibration and proper installation for each well owned by pumpers with a Baseline Pumping Allocation. The information can be submitted in any format, but all information is required to be considered complete. In the event that a required item cannot be provided, please provide a detailed explanation.

Pumper and Well Information:

- Pumper Name
- Well ID
- Well Name

Meter Information:

- Manufacturer
- Meter Type
- Meter Model
- Meter Size
- Serial Number
- Installation Date
- Certificate of factory calibration

Attachments A1 and A2 are examples of factory calibration forms.

Verification of Proper Installation

- Photographs of the well and meter that clearly show:
 - The meter make, model, and serial number
 - The meter read face
 - That there are no valves or other devices upstream of the meter that could divert water before being read by meter
- A signed letter from the manufacturer or qualified vendor verifying that:
 - There are no valves or other devices upstream of the meter that could divert water before being read by meter
 - The meter is accessible for meter reading
 - The meter has been installed according to good design practices

Attachment B is an example of an appropriate photographic log of well and meter.



Attachment A1 to Exhibit 1

Badger Meter

Order {[Order Number]}-{[Order Line Number]}

BMI Serial #:	51626244	BME Serial #:	1905-035
BMI Item #:	100-0072	BME Part #:	9010306
BMI Catalog String:	M2-030-P1-A-MWW-S-XXGF-STD		

Detector Type 2

Nominal Size:	3 Inches or 80 DN	Pressure Rating:	150 ASA
Connection:	Type 2	Material:	C-Steel
Liner:	PTFE	Max Temperature:	212 °F or 100 °C
Electrode:	Hastelloy C22	Protection Class:	IP 67
Detector Housing:	C-Steel painted	Detector Offset:	-0.0046 m/s
Detector Constant:	1858.7		


Amplifier: M2000

Mounting:	Detector mounted	Protection Class:	IP 67
Amplifier Housing:	Cast aluminium	Cable Length:	N/A
Flow Range:	2.4 to 956 GPM	Flow Direction:	Bi-directional
Full Scale Flow (Qn):	200 GPM	Power Supply:	85-265 VAC
Min/Max Alarm:	Min = 0% Max = 100%	Low Flow Cut Off:	0.2%
Empty Pipe Detection Active:	Yes	Pulse Rate:	1 pulse / Gallon
Analog Output:	4...20 mA	Pulse Width:	1:1
Pulse Output:	Active (Open Collector)	Full Scale Flow:	200 GPM
Software	1.19 ES		

	<u>Flow Rate (% of Qn)</u>	<u>% Deviation</u>
Measure Point 1:	25	0.08
Measure Point 2:	50	-0.02
Measure Point 3:	75	-0.08

The calibration of the Badger Meter ModMag M1000, M2000, M3000, M4000, M5000 and 7600P meters, sizes ¼ inch through 20 inches, are traceable to the International Systems of units using the services of the Czech Metrology Institute (CMI). The National Institute of Standards and Technology (NIST) recognizes the validity of CMI's calibration and measurement certificates.

Attachment A2 to Exhibit 1



CERTIFIED TEST REPORT

CUSTOMER: FAIN DRILLING
MODEL NO: MW503
METER SERIAL NO: 20-00488

CONFIGURATION

METER INSIDE DIAMETER: 2.988
METER OUTSIDE DIAMETER: _____
TEST DATE: 1/17/2020
TEST FACILITY: Volumetric
IDEAL TEST CONSTANT: 6000

CALIBRATION DATA

	<u>Tested TC</u>	<u>GPM</u>	<u>Accuracy</u>
1	6008	261	100.1

CERTIFIED BY: Robert Galusha ID#: 176785 DATE: 1/17/2020

* This calibration was performed on a gravimetric or volumetric test facility, traceable to the National Institute of Standards and Technology, USA. The estimated flow measurement uncertainty of the calibration facilities are:
Gravimetric +/- 0.15% Volumetric +/- 0.5%



3255 WEST STETSON AVENUE
HEMET, CA 92545 USA
PHONE (951) 652-6811 / FAX (951) 652-3078
WEB SITE: <http://www.mccrometer.com> E-MAIL: customerservice@mccrometer.com



20-00488

1/17/2020 10:04:32 AM
Version 1.2 (4/18/2007)

Attachment B to Exhibit 1

Photographs 1 to 4: Flow meter installation



Photograph 1



Photograph 2



Photograph 3



Photograph 4

Exhibit 2

Requisite Information to Verify Accuracy of Meters to the Borrego Springs Watermaster

The accuracy of the pumping meters installed at each well owned by pumpers with a Baseline Pumping Allocation, whether existing or new, must be verified by the Watermaster prior to the first meter read for the start of Water Year 2022, which starts on October 1, 2020. The accuracy of all meters must be verified annually thereafter.

The following information must be submitted to the Watermaster to verify the meter accuracy. The information can be submitted in any format, but all information is required to be considered complete. In the event that a required item cannot be provided, please provide a detailed explanation.

Pumper and Well Information:

- Pumper Name
- Well ID
- Well Name

Verification of Meter Accuracy

- A form prepared by a qualified vendor documenting the results of the meter accuracy test. The form must include and demonstrate:
 - The meter test date
 - The meter information (make, model, size, serial number, units of reporting)
 - The test information: test method, meter reads before and after test, metered flow, actual flow, accuracy of meter read.
 - The average accuracy result of at least two tests that measured meter accuracy.
- Photograph of the well meter face that verifies the beginning and end meter reads during the accuracy test. If the meter verification was performed prior after March 30, 2020 but before August 31, 2020, this information is not required.
- A signed letter from the manufacturer or qualified vendor that:
 - Reports the average accuracy (+/- %) of each meter tested
 - Indicates meters where the variability between at least two meter accuracy test results is greater than +/-5%. These meters require calibration to meet accuracy standards.
 - If a calibration is performed, submit forms documenting the calibration results and additional information from the vendor certifying the post-calibration accuracy. Calibration must be completed within 30 days of a finding that the meter does not meet the accuracy standards.

Attachments C1 and C2 are examples of meter accuracy tests performed by qualified vendors.



Attachment C1 to Exhibit 2

PUMP CHECK

Pumping Systems Analysts

Hydraulic Test Report

(951) 684-9801 • Lic. 799498 • Fax (951) 684-2988

CERTIFICATE OF ACCURACY

Customer: [Redacted]
Location: [Redacted]
Identification: [Redacted]
System: [Redacted]

Test Date: 09/17/2018

Meter Size: 6" Make: Water Specialties
Meter No: 973969-06 Register: CuFt x 100

General Data

Meter read before test: 401457 Meter read after test: 401473

Pipe ID: 8.0625 (Inch) Pipe area: 51.054 (sq.in.) Pressure: 5.0 (Lbs/sq.in.)

Test Data

Test Before Inspection

Test Equipment			Totalizer		Volume			Metered GPM	Percent of Flow
Test No.	Mano Read	Actual GPM	Second Read	First Read	Diff.	Convert to Gallons	Time in Seconds		
1	11.20	572	401461	401457	4	2,992	316.70	567	99.1%
2	11.15	569	401466	401461	5	3,740	397.50	565	99.2%
3	11.10	567	401472	401466	6	4,488	478.85	562	99.2%
Avg.		569.3					Avg.	564.6	99.2%

Remarks

34.07.466n117.43.232w
PC 3122/SCE 41078

Rhonda Steward
cn=Rhonda Steward, o=Pump
Check, ou,
email=rhonda@pumpcheck.c
om, c=US
2018.09.25 09:08:20 -07'00'

Approved _____

P.O. Box 5646, Riverside, California 92517

"Pump Testing, The Service That Pays For Itself"

Attachment C2 to Exhibit 2

McCall's Meters Inc.

Field Test Report

1498 Mesa View Street
 Hemet, CA 92543
 Tel: 951-654-3799 Fax: 951-654-3991

Utility: XXXXX
 XXXXX
 XXXXX

Date: 11-26-18
 Tech: TD & ND

Account Number: XXXX
 Meter Location:

Size: 8"
 Manuf: Water Specialties
 Type: Prop w/ transmitter
 Ser No: 20070812-06

Test Point: Remove 1" sampler before meter and outside shed

Pipe I.D. 6.000 inches
 Pipe Area: 28.27 sq. inches
 Pressure: NA psi

Meter Readings:
 Meterhead: 718122 Units: Gals x 1000
 Remote: Units:

	Meter	Trans
Drive Gear	NA	
Driven Gear	NA	

TEST BEFORE REPAIR

Test No.	Pitot Data		Subject Meter Data						
	Mano. Diff.	Pitometer Flow GPM	Totalizer Units Gals x 1000		Test Run Volume Gallons	Test Run Time		Meter Flow GPM	Indicated Meter Accuracy
			Stop Read	Start Read		Min.	Sec.		
1	5.9	166.8	614316	614315	1000.0	5	47.6	172.6	103.5 %
2									
3									
4									
5									

	Meter	Trans
Drive Gear		
Driven Gear		

TEST AFTER REPAIR

1									
2									
3									
4									
5									

Remarks: The test results indicate proper meter accuracy.

**Borrego Springs Watermaster
Qualified Vendors for Meter Verification and Calibration**

1. McCall's Meter Sales and Service, Inc.
 - a. Address and contact info
 - i. 1498 Mesa View Street, Hemet, CA 92543
 - ii. Office: (951) 654-3799
 - iii. Fax: (951) 654-3991
 - iv. <http://mccallsmeters.com/>
-

2. Pump Check
 - a. Address and contact info
 - i. P.O. Box 5646, Riverside, CA 92517
 - ii. Office: (951) 684-9801
 - iii. Fax: (951) 653-1950
 - iv. info@pumpcheck.com
 - v. <http://pumpcheck.com/>
-